

## PROJECT PROFILE: 4570 - South Western Railway 5G MMWave Build

### PROJECT SPECIFICATIONS

Status:	<b>Completed</b>
Started:	August 2021
Completed:	March 2025
Client:	Evo-Rail
Location:	Earlsfield to Basingstoke
SVR Disciplines:	Veg Clear, cable Pulling, 5G masts, Safe Walking route, Surveys, Retaining walls, Piling, route installation



### ABOUT THE PROJECT

The scope of this project is the provision of 58 off new trackside 5G Antennas and their associated ancillary equipment over approx. 70Km of Railway, starting around Earlsfield Station and go through to Basingstoke Station. All the works are along the BMLI line – from 5m 65ch to 47m 23ch

### PROJECT OVERVIEW

- Installation of 58 piled 5G connectivity masts approx. 1km apart
- Retaining wall structures around 32 piled masts
- Safe access GRP handrail
- Safe access GRP grating
- Bank reinstatement
- Type I walk route install
- Vegetation clear for safe access
- 2300m TTS90 installation
- 50m TTS200 installation
- 579m Arco on piled posts
- Safe delivery of materials by hand, RRV's and rail trolleys.
- 60+Km of cable pulled
- Installation of cabinet bases
- Provide transient welfare facilities
- Provide cable trailer and operatives
- Environmentally dispose of onsite waste

## PROJECT PROFILE: 4570 - South Western Railway 5G MMWave Build



## PROJECT PROFILE: 4570 - South Western Railway 5G MMWave Build



For more information  
please contact:

Paul Hayes  
Managing Director  
Sunville Rail Limited  
[paul.hayes@sunvillerrail.co.uk](mailto:paul.hayes@sunvillerrail.co.uk)