

PROJECT PROFILE: Lydden And Luddenham Walkways

PROJECT SPECIFICATIONS

Status:	COMPLETED
Started:	December 2021
Completed:	March 2022
Project Duration:	4 Months
Client:	Murphy's
Location:	Lydden and Luddenham
SVR Disciplines:	Walkway construction, Routeworks, Access, Vegetation clearance, Site Clearance



ABOUT THE PROJECT

This is another example of safe access walkways to sites, for our NR maintenance colleagues and future improvement projects delivering walkways of large quantities at both sites of Lydden and Luddenham in Kent.

PROJECT OVERVIEW

Sunville Rail were awarded works to clear vegetation and install a new safe walking access routes with 235M installed at Lydden and 330M installed at Luddenham to create safe walking access at both sites.

Walkway was installed using GRP grating, GRP handrail and plastic lumber to ensure a sturdy, durable and long-lasting safe walking route for access.

- * Works carried out by Sunville include;
- * Install GRP Walkway and Handrail
- * Vegetation clearance works
- * Secure Chainlink fencing
- * Site clearance
- * Routeworks
- * Safe access to track paralleling hut
- * Install new Access Gate
- * Create and install access gate signage



PROJECT PROFILE: Lydden And Luddenham Walkways



For more information please contact:

Paul Hayes
 Managing Director
 Sunville Rail Limited
paul.hayes@sunvillerrail.co.uk