



PROJECT PROFILE: STEPHENSON STREET

PROJECT SPECIFICATIONS

Started: COMPLETED
Started: June 2021

Completed: December 2021

Project Duration: 6 Months

Client: SSE

Location: WEST HAM

SVR Disciplines: CABLE INSTALL, TESTING, SHEATH TERMINATION, HV, JOINTING, CABLE

PULL



PROJECT OVERVIEW

Sunville Rail Limited successfully completed the diversion of 2 x Grid Feeders at Stephenson Street as part of the Twelve Trees Park development project.

ABOUT THE PROJECT

Berkeley Homes acquired land located in West Ham (Stephenson Street) for development. There were four existing 25kV Network Rail (NR) cables running across the northeast corner of this site. There are also 2 pilot cables running within the same line. These cables run along the boundary in London Underground Ltd land above ground on concrete posts/hangers. At a certain point, these cables become buried (in ducts) and enter the Berkeley Homes site identification and then into the Network Rail's Substation located at the northern end of the Berkeley's site.

These cables require diversion around the perimeter of the Berkeley Homes site, running adjacent to the LUL Jubilee line and then adjacent to the NWR line/Northern boundary.

Sunville Rail were responsible for:

- Production of all documentation- Testing Plans, Work Package Plans, ITP's and TBS's.
- Supply (Purchased from WRS) and Installation of 2km -of 25kV 300 mm2 Concentric Cable XLPE insulated, MDPE, Graphite
- coating 1km -10-pair pilot cable with 0.9 mm diameter cores
- Successful Jointing terminating, sheath testing and terminations. (Well Done ADHV for a great job)
- HV assessments and HV Comps for all works.
- Supply methodology and man power to pull cable and install.
- Safe unloading and transportation of cable





















PROJECT PROFILE: STEPHENSON STREET

















For more information please contact:
Paul Hayes
Managing Director
Sunville Rail Limited
paul.hayes@sunvillerail.co.uk















